

Proposal – KOLF

**Wiring Harness & Sub Harness Engine Integration
Proposal**

Wiring Harness & Sub Harness Engine Integration Proposal

< Current Spec >



- ① Male and Female Coupler Available in Harness & Sub Harness Eng



KOP/KOL STD
- 4P Delete
KOL DLX -
6P→2P

- ② ACG Sensor Coupler (Harness Wire & ACG) Supplier : Sumitomo
- Male Coupler : 32617 MCA A710 Y1
Female Coupler : 32618 MCA A710 Y1


< Proposal Logic >

Background

- Base model used separate eng sub harness for ease of assy.
- Harness Wire and Sub Harness Eng come from Same Supplier in all Models so this idea can be implemented at Harness Supplier End.
- ACG Sensor Coupler is commonization with Yazaki coupler (KONA common part) for Cost Merit.

Model	Maker Harness	Maker ACG
KOP (CRF Approved)	Minda , Dhoot	Denso
KOL	Msumi	Mitsuba
K1J	Msumi	Mitsuba
KOY	Msumi, Minda	Mitsuba

< Proposed Spec >

- ① Coupler Elimination (Male & Female) ▶ No Coupler (Std)  2P Coupler (Dlx,Std2)
- ② ACG Sensor Coupler Supplier Change Sumitomo → Yazaki ▶ Male Coupler :91771 KOJ N010 Y1
Female Coupler:91772 KWP H010 Y1

Model Wise CR			
Model	RS / Veh	Imp Month	Mil Rs.
KOP	-34.30	Dec' 21	-19.01
KOL	-41.97 (Std) -32.53 (Dlx)	Oct' 21	-6.13
K1J	-35.20 (Std/Dlx)	Oct' 21	-1.39
KOY	37.74 (Std) -25.73 (Dlx)	Nov' 21	-4.96

< SEDB Judgment & Testing Status >

Team	Judgement	Comment
Sales	0	OK, Non-Visible area
HRID	0	OK (Testing Completed KOLF)
QC HO	0	OK (Testing Completed KOLF)
MFG	0	OK (Trial Result OK)
PU	0	OK
Cert	0	OK (EMI/EMC Test Result OK)
CS	0	KOL (Only New model change Implement)

- ❑ Reporting done for above change in KOP,KOL,KOY,K1J to CPO/CQO san
- ❑ Phase 1 -> KOPG WVTA CRF Approved
- ❑ Phase 2 -> Request for KOLF WVTA Approval , Detail explanation in further slide


Change Point	Part Name	Change Details	Application				Validation						Remarks KOP Vs KOL
			KOPG		KOLF		EQ	AF			Cert.	HRID	
			STD	DLX	STD	DLX		2F	3F	4F			
1a	Harness Wire & Sub Harness Eng.	Merging of Sub Harness, Eng. with Main Wire Harness	O	O	O	X	O	O	O	O	O	O	Common with KOPG Proposal, Already CRF approved
1b		6P → 2P coupler (for Speed sensor circuit)	X	X	X	O	O	O	O	O	O	O	Explained in slide 4 (Inform to CQO in KOP CRF approval)
2	Harness Wire	Change of Ignition coil terminal Cover from Black to Transparent	O	O	O	O	O	O	O	O	O	O	Common with KOPG Proposal, Already CRF approved
3	Harness wise & ACG – Stator Comp	Sensor Module Coupler Change from Sumitomo → Yazaki	O	O	O	O	O	O	O	O	O	O	Common with KOPG Proposal, Already CRF approved
4	Harness Wire	Waterproof Joint Change : Water pad → Heat shrink tube	O	O	O	O	O	NA	NA	NA	O	O	Already Implemented from KOPA

☐ In KOLF all Design , Quality & Assembly confirmations have been done similar to KOP -> OK

☐ In KOLF DLX, Coupler change from 6P → 2P Due to speed sensor is assembled in AE.

☐ KOP Heat Shrink tube is Horizontal deployment in KOL also(Water Pad deletion)

Same as KOPG




For KOLF STD1 Variant, Eng Sub harness to be integrated with main harness.




Coupler Name : WPC 6P 025 F
Part No: 91772 - KWP- H010-Y1



Coupler Name : WPC 6P 025 M
Part No: 91771-K0J-N010-Y1



**Change : Optimize Coupler
6P → 2P**



For all Digital meter models, No of circuits in Eng sub harness to be reduced from 6 ->2.
Reason : Speed Sensor has to be assembled in AE

Circuit	Harness wire <-> ACG Sensor Module																						
Illust	Existing	Proposal																					
	 Sumitomo(Import)	 Yazaki(Local)																					
* Proposed coupler Already use in K1E, K1C, K0N, K0V																							
<table><tr><td></td><td>Sumitomo</td><td>Yazaki</td></tr><tr><td>Spec</td><td colspan="2">HES D3217</td></tr><tr><td>Insertion force of Connector</td><td colspan="2">66.7N Max (As per HES)</td></tr><tr><td>Removal Force of Connector</td><td colspan="2">66.7N Max (As per HES)</td></tr><tr><td>Stopper Point</td><td colspan="2">No Change</td></tr><tr><td>Wire Size</td><td colspan="2">No change (AVSS 0.3f)</td></tr><tr><td>Terminal Catch</td><td colspan="2">No change</td></tr></table>				Sumitomo	Yazaki	Spec	HES D3217		Insertion force of Connector	66.7N Max (As per HES)		Removal Force of Connector	66.7N Max (As per HES)		Stopper Point	No Change		Wire Size	No change (AVSS 0.3f)		Terminal Catch	No change	
	Sumitomo	Yazaki																					
Spec	HES D3217																						
Insertion force of Connector	66.7N Max (As per HES)																						
Removal Force of Connector	66.7N Max (As per HES)																						
Stopper Point	No Change																						
Wire Size	No change (AVSS 0.3f)																						
Terminal Catch	No change																						

Male Coupler			Same as K0PG
32617 MCAA710 Y1 → 91771-K0J-N010-Y1 WPC 6P 025 M → WPC 6P 025 M			
Female Coupler			
32618 MCAA710 Y1 → 91772 - KWP- H010-Y1 WPC 6P 025 F→ WPC 6P 025 F			
Condition	Harness Side	ACG Sensor Side	
Before	Female	Male	
After	Male	Female	

*Change due to accommodate tapping on harness side

Additional change: Ign coil connector cover color Black -> Transparent

Idea 3

As per request from AF :
Due to the change in process, the visibility of Ignition coil coupler connection has become difficult.
Request is to change the boot colour of coupler to transparent for better **Quality control and confirmation.**

Black -> Transparent



Change Point	Part Name	Change Details	Application				Validation						Remarks KOP Vs KOL
			KOPG		KOLF		EQ	AF			Cert.	HRID	
			STD	DLX	STD	DLX		2F	3F	4F			
1a	Harness Wire & Sub Harness Eng.	Merging of Sub Harness, Eng. with Main Wire Harness	O	O	O	X	O	O	O	O	O	O	Common with KOPG Proposal, Already CRF approved
1b		6P → 2P coupler (for Speed sensor circuit)	X	X	X	O	O	O	O	O	O	O	Explained in slide 4 (Inform to CQO in KOP CRF approval)
2	Harness Wire	Change of Ignition coil terminal Cover from Black to Transparent	O	O	O	O	O	O	O	O	O	O	Common with KOPG Proposal, Already CRF approved
3	Harness wise & ACG – Stator Comp	Sensor Module Coupler Change from Sumitomo → Yazaki	O	O	O	O	O	O	O	O	O	O	Common with KOPG Proposal, Already CRF approved
4	Harness Wire	Waterproof Joint Change : Water pad → Heat shrink tube	O	O	O	O	O	NA	NA	NA	O	O	Already Implemented from KOPA

☐ In KOLF all Design , Quality & Assembly confirmations have been done similar to KOP -> OK

☐ In KOLF DLX, Coupler change from 6P → 2P Due to speed sensor is assembled in AE.

☐ KOP Heat Shrink tube is Horizontal deployment in KOL also(Water Pad deletion)

Waterproof Joint Sealing Process Change : Water pad to Heat shrink tube

Waterproof Joint Process: No Change



1. Wire cutting & stripping.



2. Middle Splicing.




3. Joint Crimping

Waterproof Sealing Process: Change in Sealing (Same as KOP)

Existing



Proposal



- Heat Shrink tube is already being used in Dhoot & Minda Sai Harness maker(KOP,KOY)
- Msumi is already using in KONF Model
- Now proposal for horizontal Deployment in KOLF

Waterproof joint to be change from Water pad to Heat shrink tube

Denso test Results for KOLF Engine Sub Harness elimination CR Idea

Category	Test Items	Criteria	Results	Judgement				
Wiring	Wiring and parts L/O	Must be satisfied in check list of A024-1-1-1	Found OK as per A024-1-1-1	OK				
Ignition	Demand & Supply spark performance	Supply voltage must exceed demand voltage	Min. Voltage gap is 4.6KV at 3000 r/min (Snap)	OK				
Radio Noise	Broadband Noise (Based on UN/ECE R10-03)	The noise for the CBU must be no higher than the test evaluation values	Minimum margin observed was <table><tr><td>STD</td><td>Peak 8.5dB / 857.6MHz</td></tr><tr><td>DLX</td><td>Peak 5.65dB / 841.15MHz</td></tr></table>	STD	Peak 8.5dB / 857.6MHz	DLX	Peak 5.65dB / 841.15MHz	OK
	STD	Peak 8.5dB / 857.6MHz						
	DLX	Peak 5.65dB / 841.15MHz						
	Narrowband Noise (Based on UN/ECE R10-03)	The noise for the CBU must be no higher than the test evaluation values	Minimum margin observed was <table><tr><td>STD</td><td>Average 1.31dB / 70MHz</td></tr><tr><td>DLX</td><td>Average 4.42dB / 55.65MHz</td></tr></table>	STD	Average 1.31dB / 70MHz	DLX	Average 4.42dB / 55.65MHz	OK
STD	Average 1.31dB / 70MHz							
DLX	Average 4.42dB / 55.65MHz							
Environmental Compatibility	Water ingress test	When vehicle is high pressure water washed. No engine problem, malfunction is allowed.	No electrical malfunction observed.No water entry inside electrical parts observed.	OK				
	Pool riding	No engine stop or malfunction is allowed	No water ingress and no electrical malfunction observed.	OK				
	Vehicle wash with hose	No engine stop or malfunction is allowed	No water ingress and no electrical malfunction observed.	OK				
	Thermocycle respiration test for harness	Water ingress is not allowed to the parts designed to be water proof due to thermocycle respiration	No water ingress observed	OK				
	UN/ECE R10-03	No electrical malfunction is allowed.	No malfunction observed.	OK				
	Mobile phone substitution test	No electrical malfunction is allowed.	No malfunction observed.	OK				
	Ignition noise	There must be no malfunctions.	No malfunction observed.	OK				
	Each electrical load noise	There must be no malfunctions.	No malfunction observed.	OK				

- DR test completed in both STD1 & DLX Variants

All tests confirmed for KOLF model and found OK.

AF Confirmation for STD/DIX Models for all factories (2F/3F/4F)

Cycle Time Study		Case ① - Mechanical Meter [KOP, KOY Std1, KOL Std1]		Case ② - Digital Meter [KOL Std2 & Dlx, KOY Dlx, K1J]	
Area		AE2F	AF2F	AE2F	AF2F
Change Points [Process time]		Sub Harness Eng. Deleted	New Wire Harness [Old Harness + Sub Harness Eng. – 2 Couplers]	Sub Harness Engine [Ignition & Temp. Sensor Branch Eliminated]	New Wire Harness [Old Harness + Ignition & Temp. Sensor Branch]
Process Feasibility		Yes	Yes	Yes	Yes
Cycle time (secs)	Before	10 [Assy - 7, Part Load - 3]	-	7	-
	After	0	47	0	47
	Impact	-10	+47	-7	+47
Cost Impact [Rs/Veh] [Manpower Cost/Sec @0.05]		-0.5	+2.35	-0.35	+2.35
		+1.85		+2.0	
Request Point			Action Taken		Status
Request 1:- Addition of 2MP/Shift/Line to compensate the increase in CT due to process Increase .			Cost considered in CR based on Manpower request by AF		<input type="radio"/>
Request 2:-Change of Boot Colour of Ignition Coil from Black → Transparent			Proposal discussed and agreed by HRID to implement in Drawing		<input type="radio"/>

Feasibility is confirmed from 2F/3F/4F & both the request are considered to Apply this Proposal.

CQO San Comment during K0PG CRF :

- Trial event to be done in all factories(In Consensus Plant head)

Trial Done & Explanation Done to CQO san for K0PG, CRF Approved

Same activity has been done in K0LF, explanation in next slides

AF Confirmation of Online Trial Event

- ❖ Proposal was discussed for conducting Trials in each factory
- ❖ Consensus done with each factory
 - 2F : Miyagawa San ,Plant Head
 - 3F : Yamamoto San ,Plant Head
 - 4F : Plant Head
- ❖ Date fixed for Offline & Online Training/Trial in each factory.

Control Item	Items		2F	3F	4F
KOL	Vehicle Availability		1	3	3
CR Proposal	Proposal explanation to AF Team		22 nd July	22 nd July	22 nd July
	Proposal Explanation to OH (Along with KOP)		24 July	24 July	24 July
Document	Process Plan		16 th Aug	16 th Aug	16 th Aug
	PQCS				
	WPC Check Sheet				
	OPS				
	Training Record				
Training	Off Line		16 th Aug	16 th Aug	16 th Aug
	On Line				
Online Trial	As per WPC Check Sheet		18 th Aug	18 th Aug	17 th Aug
	As per OPS Verification				
	Cycle Time				
	Process Confirmation				

Trial conducted as per above Dates

KOLF Trial Status 2F/3F/4F

Parameter	Criteria	2F Status	3F Status	4F Status	Status
Documents	Process Plan Change	Done	Done	Done	○
	PQCS	Done	Done	Done	○
	WPC Check Sheet	Done	Done	Done	○
	OPS	Done	Done	Done	○
Handling of New Wire Harness	Sub assy → Any concern	No Concern Checked on Line	No Concern Checked on Line	No Concern Checked on Line	○
	Main Line → Any Concern				
Training	Training Manpower → 4 Nos	Training Done → 4Nos	Training Done → 4Nos	Training Done → 4Nos	○
	Training skill Requirement for MP start → L2	Training Skill Achieved → L2	Training Skill Achieved → L2	Training Skill Achieved → L2	○
	Training Skill Matrix	Done	Done	Done	○

2F confirmation

MOM with Miyagawa San & Takita San Cc Plant Team		Target Date	Miyagawa San - AF	Takita San - CIC
1 Online Trial of KOLF Vehicle - Assembly		18th Aug		
2 Observation from Miyagawa san --> More training required at Temperature Oil sensor connection(KOLF 3D layout to be shared to AF)		18th Aug	Sunil San - AF2F	
3 Document & Activities			Rahul San - AF2F	
Process Plan Change		TBD by 19th		Sherat Gupta - CIC
PQCS		TBD by 19th		
OPS		TBD by 19th		
WPC Check sheet		TBD by 19th		
Operator Training & Skill up		TBD by 19th		
Training Skill Matrix Final		TBD by 19th		

3F confirmation

Reporting to Yamamoto San, Plant Head

The screenshot shows a detailed report for the KOLF trial. It includes a 'Cost Saving Proposal' table with columns for 'Activity', 'Status', and 'Remarks'. The 'Implementation Schedule' is a Gantt chart showing the timeline for various activities from August 1st to August 18th. The report is addressed to Yamamoto San, Plant Head.

4F confirmation

Reporting to Plant Head


The screenshot shows an email from Sherat Gupta to the Plant Head. The email is titled 'FW: Quick CR Thread KOLF Harness Connection - CRF for approval (AF)'. It includes a 'Dear Sir,' salutation and a request for a scanned copy of the document. The email is dated 20 August 2021 19:06.

Trial is done and confirmation Received from all factory 2F/3F/4F

Summary of Trials & Reporting done to Factory

Plant	Trial Summary	Resp	Tgt Date
2F	Miyagawa San : Genba check done during Trial and result is Satisfactory Comment : More Training required at Temp Oil Sensor Connection	AF	PP3
3F	Yamamoto San : Genba check done during Trial and result is Satisfactory. Also Reporting is done to Plant Head during KOLF WVTA E1-2	AF	Done
4F	Trial done and result found satisfactory (Same has been reported to their Plant Head)	AF	Done

KOLF Implementation Schedule



Request to CQO/QC OH San for Go Ahead & implementation of Proposal.

Thanks